

219 S. Cook Street – Contributing



ARC 01-09

ARC 09-03 – demolition of a contributing dwelling and contributing detached garage

Located at 219 S. Cook Street is a two-story, frame, gabled ell plan dwelling constructed ca. 1862 and extensively remodeled ca. 1920 and 1950. The dwelling has an exterior of asbestos shingle siding, a gable roof of asphalt shingles with gable returns, a continuous brick foundation covered with stucco and an interior central brick chimney. On the main (E) façade is an shed roof porch with an added second story. The lower façade of the porch has been enclosed with rectangular, two-over-two double hung wood sash windows. The upper façade of the porch has also been enclosed with two-over-two double hung wood sash windows. Both porches have an exterior of asbestos shingle siding. The main entrance has a ca. 1990, nine-light and cross-hatch wood door with original two-vertical-light glass and wood sidelights with a river rock stoop and wrought iron railings. Also on the main façade is a hipped roof projecting bay window with a central fixed light window flanked by one-over-one double hung wood sash windows and supported by an asbestos covered base. On the north façade is a two-story wood staircase. Windows are original, rectangular, two-over-two double hung wood sash with wood cornice surrounds and flanking wood plank shutters.

On the rear façade is an original shed roof wing, which possibly was an original rear porch at one time. The wing has been partially enclosed and has two entrances beneath a shed roof porch supported by wrought iron posts, railings on a poured concrete floor. Also attached to the rear façade is an original single-story rear wing with an added second story. Windows in the addition are one-over-double hung metal sash windows and single-light fixed windows. A rear wood staircase leads to a second floor entrance with a shed roof canopy over a ca. 1985 glass and aluminum door.

The property retains its original cistern block in the south façade side yard and to the rear of the dwelling is an original single-bay garage with a front gable roof of asphalt shingles, an exterior of weatherboard siding, a ca. 1980 metal panel overhead door and vertical board in the gable field.

Contributing

