

115 E. Lincoln Avenue – Noncontributing



Located at 115 E. Lincoln Avenue is a one- and one-half story, frame, gabled ell plan dwelling built ca. 1940. The dwelling has an exterior of aluminum siding, a multi-gabled roof of asphalt shingles, an exterior end brick chimney and a continuous poured concrete foundation. On the main (N) façade is a shed roof entry porch supported by one square wood post set on a concrete stoop. The main entry has a ca. 1990, nine-light glass and two-panel vinyl door with an aluminum and glass storm door. Windows are replacement; one-over-one double hung wood sash windows with flanking metal shutters. At the roofline on the main façade is a gable roof dormer with original paired set of four-over-four double hung wood sash windows.

Located off the southwest corner of the dwelling is an original, single-bay, hipped roof garage with exposed roof rafters, an exterior of weatherboard and original, double vertical board hinged doors. **Contributing**



213 E. Lincoln Avenue - Contributing



This is a small, one-story, frame, front gable Folk dwelling built ca. 1920. The dwelling has a roof of asphalt shingles, an aluminum siding exterior and an interior metal flue. On the main (N) façade is a full-width, hipped roof porch which has been enclosed and the main entrance has now been relocated to its north façade. The entrance retains its original, single-light glass and wood door and an original, three-light glass and wood exterior storm door. On the west façade is a shed roof addition with a row of single-light, fixed windows near the eaves. The east façade has eight-over eight, double hung wood sash windows. The dwelling appears to have been associated with 215 East Lincoln and was possibly an in-law cottage or shop.

This dwelling has deteriorated over the years. The ARC has reviewed the state of the dwelling, and though it is a contributing structure, the amount of repair and reconstruction work that would be necessary to restore the structure is such that demolition of this structure is acceptable.

215 E. Lincoln Avenue – Contributing



Located at 215 East Lincoln Avenue is a one- and one-half story asymmetrical Folk dwelling built ca. 1915. The dwelling has a hip and gable roof of asphalt shingles, an exterior of aluminum siding, a continuous poured concrete foundation and an exterior end aluminum-sided chimney. On the main (W) façade is a ca. 1960, incised porch with a concrete block foundation, square wood posts and a wood railing. Over one of the two entries is a gable roof canopy with aluminum siding in the gable field. Two entries are located on the main façade. One entry has a ca. 1940, single-light and four-wood panel door while the secondary entrance has a two-horizontal-light glass and wood panel door. Both doorways have glass and aluminum storm doors. Windows are original, one-over-one double hung wood sash with aluminum-covered surrounds and flanked by vinyl shutters. On the main (W) façade is a paired set of three-light metal casement windows. A small, gable roof addition is located on the rear façade.

Off the southwest corner of the dwelling is a one-bay, frame, ca. 1930, garage with a hipped roof of asphalt shingles and original twenty-wood panel overhead track door flanked by vinyl shutters. **Contributing**



301 E. Lincoln Avenue – Noncontributing



Community Church of Barrington

The Community Church of Barrington was constructed in 1950 as a gabled ell building in the Colonial Revival style. It has a concrete foundation, hipped and gable roof of asphalt shingles, and exterior of stretcher bond brick. On the main (N) façade is an entrance with original double wood paneled doors, a five-light transom, Doric pilasters and an elliptical pediment. Windows are original six-over-six rectangular wood design with multi-light arched transoms. Inset into the gable field and tower are oculus windows. Both the tower and the main building have brick quoins at the corners. The central frame tower rests on a brick base and is octagonal in design with louvered vents. At the rear is an added education wing.



312 E. Lincoln Avenue – Contributing



This is a two-story asymmetrical Queen Anne-influenced Folk dwelling built ca. 1890. The dwelling has a central hipped roof of asphalt shingles with projecting gable bays, a continuous stone foundation, a central interior brick chimney and an exterior of aluminum siding. On the southwest corner of the projecting gable bay's first floor is a chamfered corner. Adjacent to the chamfered corner on the east side is a fixed, single-light Victorian picture window with a single light transom. The main (S) façade has a ca. 1940, two-story, flat roof porch enclosed on both levels with Craftsman-style, four-over-two, fixed-light glass and wood windows and an exterior of aluminum siding. The porch was originally a one-story porch and the second story added ca. 1915. The dwelling's original single-light glass and wood door has been moved to the first floor porch entrance and is flanked by two-light sidelights. The main entrance leading to the interior from the porch is a ca. 1940, fifteen-light glass and wood door. The interior of the porch retains a section of the original narrow weatherboard exterior. Windows are original, one-over-one double hung wood sash. In the gable field on the main façade is a single-light casement window above which is a triangular louvered attic vent. Located on the rear façade is a two-story wing.

A ca. 1975, frame garage with a hipped roof of asphalt shingles, a poured concrete foundation and an exterior of aluminum siding is located off the northeast corner of the dwelling. On the rear (N) façade of the garage is a shed roof addition. **Noncontributing**



316 E. Lincoln Avenue – Contributing



Located at 316 East Lincoln Avenue is a two-story rectangular American Foursquare style dwelling built ca. 1902. The dwelling has a hipped roof of asphalt shingles, an interior brick chimney, a continuous brick foundation and an exterior of weatherboard siding. On the main (S) façade is a one-story, full-width porch enclosed with large, four-light fixed glass and wood window panels and weatherboard siding. The entrance to the porch has a ca. 1980, fanlight glass and wood door. The main entrance to the house from the porch retains its original, single-light glass and wood door. Windows are original, one-over-one double hung wood sash. At the roofline of the main façade is a shed roof dormer which has a pair of ca. 1960, two-light sliding track metal windows one of which has an air conditioning unit in the frame. On the west façade is a small, gable roof dormer with a triangular window. On rear façade is a ca. 1980, two-story, frame porch with a two-story wood staircase attached to an original, two-story rear wing.

317 E. Lincoln Avenue – Contributing



This is a one-and-one-half-story, frame, gable front Folk dwelling built ca. 1890. The dwelling has a poured concrete foundation, a front gable roof of asphalt shingles, an exterior brick chimney and an exterior of aluminum siding. On the main (N) façade is a full-width, hipped roof porch enclosed ca. 1960 with five-light, jalousie metal windows, weatherboard siding and an aluminum and glass storm door. Windows are original two-over-two horizontal and four-over-four double hung wood sash. Within the enclosed porch on the main façade is an original, single-light fixed picture window flanked by two-over-two double hung wood sash windows and an original six-light and wood panel door with a wood surround leading into the dwelling from the porch. On the west façade is an added shed roof aluminum carport supported by wrought iron posts. On the rear façade is a ca. 1960, hipped roof wing.

Off the rear of the dwelling, down a slight slope and beneath a large weeping willow tree is a ca. 1904, two-bay, frame garage with an exterior of weatherboard and aluminum siding, a front gable roof of asphalt shingles, a concrete block foundation and two, ca. 1930, vertical metal panel overhead track doors. **Contributing**

