

127-129 W. Lincoln Avenue – Contributing



Located at 127-129 W. Lincoln is a two-story asymmetrical Italianate style dwelling built ca. 1875. The dwelling has a brick foundation, a hipped roof of asphalt shingles, an interior brick chimney and an exterior of aluminum siding. The primary entrance faces the east façade and not the Avenue façade. On the east façade is a single-story entry porch with a hipped roof supported by original milled columns, milled brackets, wood dentils and a railing and frieze of milled cut-out panels. The main entrance retains its original, five-panel wood door with a projecting bracketed cornice with wood dentils. Also on the east façade is a single-story bay window with three, one-over-one wood sash windows, a bracketed cornice and wood dentils. At the northeast corner of the building is a two-story, rectangular, gable roof bay with large fixed one-light windows with three, stained glass sections. Each window is outlined with wood pilaster strips and bulls eye corner blocks. Below the first floor window are arched wood panels with pellet molding and below the second-story bay window are inset wood panels. On the north façade is a picture window with a single-light window fixed with three, stained glass sections. Windows overall are one-over-one double hung wood sash with bracketed cornices and wood dentils. At the roofline are paired eave brackets and gable returns. In the gable fields are circular attic vents with frame keystones and shoulders. On the west façade is an entrance with an original entry porch reconstructed ca. 1950 with square posts.

