

229 W. Lincoln Avenue – Contributing



ARC 05-06 – demolish existing detached garage and reconstruct a new detached garage as well as remodel existing front porch

Located at 229 W. Lincoln Avenue is a one-and-one-half-story side-gabled Craftsman dwelling built ca. 1920. The house has a roof of asphalt shingles, an interior brick chimney and an original exterior of stucco. On the main (N) elevation is an original gable roof porch enclosed with four-over-one, vertical-light double hung wood sash windows. The main entrance has an original, four-light glass and wood door with original, narrow, two-light glass and wood sidelights and an original, four-light transom. Windows in the dwelling are original, three-over-one-vertical light double hung wood sash with wood surrounds. On the main façade roofline is a large shed roof dormer with a set of four, two-over-one double hung wood sash windows. On the east elevation is a projecting, hipped roof bay with four, narrow, single-light windows with two-light transoms. Adjacent to this bay is a row of three, three-vertical-light glass and wood windows. The dwelling and enclosed porch have exposed roof rafters and knee brace brackets at the eaves.

To the rear of the dwelling is an original, gable front, frame garage with a front gable roof of asphalt shingles, an exterior of wood shingles and two, triple-sectioned, four-light and four-rectangular-wood-panel sliding garage doors. In the gable field is a four-light fixed attic window with a wood surround. **Contributing**

