ORDINANCE NO. 2026-4599

ORDINANCE AUTHORIZING AND APPROVING AWARD OF A CONTRACT TO CHARLES EQUIPMENT ENERGY SYSTEMS FOR AN EMERGENCY TRANSFER SWITCH INSTALLATION AND OTHER ELECTRICAL MODIFICATIONS AT THE VILLAGE'S PUBLIC SAFETY BUILDING

WHEREAS, the Corporate Authorities of the Village of Barrington (hereinafter sometimes referred to as the "Village"), Cook and Lake Counties, Illinois have determined that it is necessary, advisable, and in the best interests of the Village and its residents to make certain emergency repairs at the Village's Public Safety Building, and therefore, the Village solicited and received a proposal from Charles Equipment Energy Systems for such emergency transfer switch installation and other electrical modifications (the "Work"); and

WHEREAS, the Corporate Authorities of the Village have determined that Charles Equipment Energy Systems (hereinafter sometimes referred to as the "Contractor") is qualified to perform in accordance with Charles Equipment's proposal for the Work for a not-to-exceed contract price of $28,538.00; and

NOW, THEREFORE, BE IT ORDAINED by the President and Board of Trustees of the Village of Barrington, Cook and Lake Counties, Illinois, in exercise of the authority of this Village as a Home Rule unit, as follows that:

SECTION 1: The Corporate Authorities of the Village hereby find that the recitals hereinabove set forth are true and correct and are incorporated into the text of this Ordinance as their findings of fact to the same extent as if such recitals had been set forth herein in their entirety.

SECTION 2: The Village hereby approves and accepts the proposal dated January 16, 2026 submitted by Charles Equipment Energy Systems for the Work at a total not-to-exceed cost of $28,538.00.

SECTION 3: The Village President is hereby authorized to execute the Proposal with Charles Equipment Energy Systems (the "Contractor"), in substantially the form attached hereto as Exhibit A and thereby made a part hereof for the Work, and the Village Clerk is hereby authorized and directed to attest thereto and to deliver to the Contractor an executed Agreement for the Work and to do all things necessary and essential including the execution and delivery of any other documents necessary or appropriate to implement the subject Agreement and make the required transfer switch installation and other electrical modifications at the Village's Public Safety Building as herein authorized pursuant to 65 ILCS 5/8-9-1, waiving any and all requirements for competitive bidding otherwise required by law and said Agreement is hereby specifically authorized, ratified and approved by the Corporate Authorities of the Village pursuant to Section 1-6A-6 of the Barrington Village Code.

SECTION 4: This Ordinance shall be in full force and effect from and after its passage and approval as provided by law.

PASSED THIS 26 DAY OF JANUARY, 2026 BY ROLL CALL VOTE AS FOLLOWS:

AYES: Trustees Lohmeyer, Sholeen, Wondrasek, Duncan, Prigge, Klauer and President Moran

NAYS: NONE

ABSENT: NONE

ABSTAIN: NONE

APPROVED THIS 26 DAY OF JANUARY, 2026

Michael Moran, Village President

ATTESTED AND FILED THIS
26 DAY OF JANUARY, 2026

James P. Dillon, Village Clerk

Village of Barrington
CORPORATE
SEAL
Cook & Lake Counties, IL

EXHIBIT A

"CHARLES EQUIPMENT ENERGY SYSTEMS " PROPOSAL DATED JANUARY 16, 2026
RECEIVED FROM CHARLES EQUIPMENT ENERGY SYSTEMS

CHARLES EQUIPMENT ENERGY SYSTEMS

"Engine Power Specialist since 1960"

530 Santa Rosa, Des Plaines IL. 60018

Office; (630) 834-6000 Fax: (630) 543-4174

"Take advantage of our full line of rental generators, light towers, ac units, heaters and power distribution equipment."

QUOTATION NO. 4 6 0 2 **DATE:** January 16, 2026

TO: Barrington Public Safety
400 Northwest Highway
Barrington, IL. 60010

REF: Building Switchgear
Upgrade/modification.
Attn; Steve Krantz
Office: 1 (847) 304-3418
Mobile: 1 (224) 363-0708

Charles Equipment Energy Systems is pleased to have the opportunity to quote the following:

Provide one (1) new ASCO 800 AMP automatic transfer switch (ATS) and one (1) new 800 AMP circuit breaker. Inform utility (Comm Ed) to open utility feed, verify no voltage present. Remove the defective existing two beaker style disconnect/ATS, modify the existing switchgear line up to install the 800 AMP breaker as the main disconnect, cable from the existing utility (Comm Ed) leads to newly flush mounted breaker. Mount the new 800 AMP ATS in the adjacent panel, cable the utility feed side to/from the new 800 AMP breaker, cable the existing emergency generator feeds to the emergency side of the new 800 AMP ATS. Cable the load side of the ATS directly to the existing buss bar. Meter out leads, verify proper installation and phase rotation.
Test the new 800 AMP ATS by reconnecting the remote start wiring and witness the emergency generator start as needed. Manually shut down the emergency generator. Inform utility to restore power, verify as needed. Put the emergency generator back in auto mode, verify as needed. Simulate an outage by opening the newly installed 800 AMP breaker, witness the operation as designed, closed the breaker and witness a normal shutdown. Leave system in auto. We anticipate an estimated down time of 6-8 hours.

Quoted Price $26,864.00...plus tax and permits if applicable.

Current lead time is 8 weeks, E-orders would be placed in an effort to expedite but no promises can be made.

Available Option

CEES has a 1200 AMP ATS in stock that could be used in lieu of the above quoted 800 AMP ATS. There would be a price increase of $1,674.00 if you choose this option.

* This quote is based on the above quoted scope of work. Any additional request, changes or modifications would be based on time and material. Final load confirmation must be confirmed that 150 kW is suffice.

WARRANTY: Warranty is based on the manufacture published policy

STANDARD TERMS: Charles Equipment Energy Systems standard terms and conditions of sale, whether attached hereto or not, a copy of which is on file at the Charles Equipment Energy Systems Corporate office. Charles Equipment Energy Systems hereby objects to any additional or different terms set forth in Purchaser's request for quotation, specification, purchase order, or any other document of purchaser. Acceptance of additional or different terms must be specifically agreed to in writing by Charles Equipment Energy Systems.

PROJECT TERMS: Net 30 days with authorized PO. **FOB:** Jobsite

QUOTATION EXPIRES: 12 /31 / 2026 **DELIVERY:** 8- weeks.

Accepted: Village of Barrington
(Company)

Signed: _____

Title: Village President **Date:** 01/26/2026

Respectfully submitted,
Charles Equipment Energy Systems

Michael Biehl

Michael Biehl Sr. CEES VP